



FAMILY RUN BUSINESS
EST 1970

AMBASSADOR POOLS
MAKING LEISURE A PLEASURE

Commissioning Guide

- 1) Make sure the pool is full of water, it is difficult to prime the pump if the pool is only three quarters full or less.
- 2) Remove any debris from the pool with leaf net.
- 3) Replace all drain plugs in heater, filter, pump etc. Reconnect any Pipework.
- 4) Remove any plugs, etc from pool shell fittings.
- 5) Select "backwash" position on multiport, prime up pump and start filter pump. Run for approximately three minutes to remove any debris and commence filtration.
- 6) Following the winter there will usually be an accumulation of dust or debris on the pool bottom that requires vacuuming to waste. Select "waste" position on the multiport and prepare the pool vacuum. The pool vacuuming can now be carried out and the dust and debris discharged to waste.
- 7) Check pH of the water and adjust as necessary.
- 8) Commence and follow manufacturers instructions in regard to disinfection routine. This will usually involve shock dosing the pool with the disinfectant before using a maintenance dose and the addition of an algaecide.
- 9) If required switch on pool heating.
- 10) Cover pool with solar cover if applicable.

If you need any further assistance please do not hesitate to contact us, we will be more than happy to help with any problems or queries you have.

Showrooms: Ringwood 01425 477050. Southampton 01489 573077
West Stour 01747 839600
Email sales@ambassadorpools.co.uk